


CONTAINERS

Roll-Off Container



Roll-Off Container

| SIZE | MODEL | (A) HEIGHT INSIDE | (B) HEIGHT OUTSIDE | (C) WIDTH OVERALL | (D) LENGTH OVERALL | APPROX. WEIGHT |
|--------|---------|-------------------|--------------------|-------------------|--------------------|----------------|
| 11 YD* | ROT11 | 43" | 55" | 96" | 12' 9" | 2,930 LBS. |
| 15 YD* | ROT15 | 43" | 55" | 96" | 16' 9" | 3,680 LBS. |
| 20 YD | ROT20 | 43" | 55" | 96" | 22' 9" | 4,520 LBS. |
| 25 YD | ROT25 | 52" | 64" | 96" | 22' 9" | 4,850 LBS. |
| 30 YD | ROT30 | 62" | 74" | 96" | 22' 9" | 5,170 LBS. |
| 40 YD | ROT40 | 84" | 96" | 96" | 22' 9" | 6,040 LBS. |
| 45 YD | ROT45 | 94" | 106" | 96" | 22' 9" | 6,350 LBS. |
| 45 YD | ROT 45X | 84" | 96" | 96" | 24' 9" | 6,470 LBS. |
| 50 YD | ROT 50 | 94" | 106" | 96" | 24' 9" | 6,890 LBS. |

STANDARD DECK

- 3/16" PL. Floor Sheet
- 3" Structural Channel on 20" Centers
- 3/16" PL. Gussets on every other Cross Member
- 6" x 2" x 3/16" Tube One Piece Main Rail
- Four 8" diameter x 10" LG. Heavy Duty Wheels
- 4" OD x 6" LG Front Roller w/1 1/2" Pin and Grease Fitting
- 1" Certified Hook Plate (w/lifetime guarantee)
- 1 1/4" Certified Plate Cable Hook (w/lifetime guarantee)
- 1 1/2" Plate Solid Bullnose

FRONT AND SIDES

- 11 Ga. Sheet with Tie Down Bar and four Tie Down Hooks
- 11 Ga. One Piece Formed Dog House
- 4" x 3" x 11 Ga. Top Tube
- 11 Ga. 3" x 5" Formed 4-way Bend Side and Front Stiffener Columns on 24" Centers. Columns have notches at bottom to prevent moisture retention
- 11 Ga. Formed Corner Post wraps around for extra strength and stability with notches at bottom to prevent moisture retention
- Two Vertical Formed Bulkhead Stiffeners with notches at bottom to prevent moisture retention
- * Side stiffeners on 30" centers

REAR CORNER POST

- Latch Side 4" x 3" x 11 Ga. Tube
- Hinge Side 3" x 8" x 3/16" Formed Stiffener 4-way Bend

REAR DOOR

- 11 Ga. Sheet w/3" x 4" x 11 Ga. Tube Frame and 3/8" Safety Chain
- Hinges 1/2" x 9" x 9" and 1/2" x 3" x 9" Plates with 2" OD Mechanical Tube Bushings with Grease Fittings and one 3/16" Cold Rolled Pin
- Non-Sagging Door is designed to rest on the floor of the container
- Tie Down Hooks

DOOR LOCK

- Vertical Lift Handle System. Semi-automatic Cam Locking System with cams and Self-Aligning Keeper. The Vertical Lift Handle is securely welded to a cam style for easy operation. Handle is secured by a 3/4" solid pin, 180° turn keyway locking system.



NOTE: OPEN TOP CONTAINERS can be stacked on a oad. This saves freight cost per container. However, when stacking and unstacking, doors have to be removed and re-hung, and the containers may be scratched or dented. We cannot be responsible for this happening since it is unavoidable when stacking containers.